

Concentration Limit Table

Winmalee Wastewater Treatment Plant

EPL 1963

Updated 10-08-2023

Sydney Water's treatment plants operate under environmental protection licences issued by the NSW Environmental Protection Authority (EPA). For each monitoring/discharge point the concentration of a pollutant must not exceed the concentration limits specified for that pollutant in the table.

pollutant	unit of measure	3DGM limit	50 percentile limit	80 percentile limit	90 percentile limit	average limit
aluminium	µg/L	-	-	-	270	190
biochemical oxygen demand	mg/L	30	10	-	15	-
<i>Ceriodaphnia dubia</i> immobilisation (EC50)	% effluent by volume	-	50	-	-	-
chlorine (total residual)	mg/L	-	-	-	0.1	-
cobalt	µg/L	-	-	-	-	-
copper	µg/L	-	-	-	9	7
diazinon	µg/L	-	-	-	0.1	0.2
faecal coliforms	cfu/100ml	-	-	200	-	-
iron	µg/L	-	-	-	880	650
nitrogen (ammonia) ¹	mg/L	-	2	-	5	-
nitrogen (total) ¹	mg/L	-	15	-	20	-
phosphorus (total)	mg/L	-	2	-	3	-
total suspended solids ¹	mg/L	15	10	-	15	-
zinc	µg/L	-	-	-	33	25

Licence limits for *Ceriodaphnia dubia* immobilisation (EC50) and sea urchin sperm fertilisation (EC50) are breached if the result is below the EPA specified limit value.

3 Day Geometric Mean (3DGM) is a way to average a set of values and is commonly used with water quality assessments which show a great deal of variability. 3DGM is calculated by multiplying the results of the analysis of three samples collected on three consecutive days and then taking the cubed root of that amount.

A licence condition with a 100 Percentile Limit means that 100% of samples (or all samples) taken must not exceed the limit for that pollutant. This can be extrapolated for other percentiles, for example an 80 Percentile Limit means that 80% of samples taken must not exceed the limit for that pollutant within the annual licence period.

¹As per Condition L3.9 of EPL 1963, revised concentration limits for Nitrogen (ammonia), Nitrogen (total) and Total Suspended Solids are applicable from 7 April 2021 until 31 December 2023 whilst Winmalee WRRF is undergoing a major upgrade.