

- NOTES:
- MIN ANGLE BETWEEN CENTRE LINES OF INLET SEWERS IS 60°.
 - INSTALLATION OF THE INLET AND OUTLET SEWERS AND BENCHING MAY BE COMPLETED IN THE FACTORY.
 - FOR DN1050 MAINTENANCE HOLES UP TO 2 ≤ DN225 SEWER INLETS CAN BE INSTALLED. FOR DN1200 MAINTENANCE HOLES UP TO 3 ≤ DN225 SEWER INLETS CAN BE INSTALLED.
 - FOR DN150 SEWER CORE Ø200 HOLES, FOR DN225 SEWERS CORE Ø300 HOLES.





TABLE 1 - BASE SLAB DIMENSION	
INTERNAL DIAMETER 'A'	EXTERNAL TOE DIAMETER 'B'
1050	1630
1200	1900