

Gerringong/Gerroa Water Reclamation Plant Report

Name of wastewater treatment plant Gerringong/Gerroa Water Reclamation Plant	
--	--

System Summary	Projected			
System Summary	2020	2026	2036	2056
Gerringong/Gerroa WRP ADWF (ML/d)	1.28	1.35	1.40	1.46
Gerringong/Gerroa WRP load (EP _{COD})	7,494	7,904	8,196	8,548

Treatment capacity constraints for 2022 – 2036	Estimated year of exceedance	
None identified.	N/A	

Summary of servicing strategy for 2022 - 2036

Continued treatment of current and future population.

Treated effluent to agricultural irrigation, sand dune system or Crooked River (if sand dune system full).

Treatment plant operated by service partner on Sydney Water's behalf.

The servicing strategy was informed by the Kiama Growth Servicing Options Assessments (2021)

Anticipated augmentation and upgrades for 2022 – 2036					
Year commissioned	Description	Approximate capital cost (\$M)	Impact on servicing capacity		
N/A		None identified.			

Further investigations				
No further investigations underway.				